

STORAGE SHED - PLANS.COM
SHED PLAN #1995 12X16 HIP ROOF

Material	Description	Qty	Units
Floor Screws		1	ctn
2x4 Precut (B)	2"x4"x92 5/8"	46	each
Wall Stud	2"x4"x31"	4	each
Jack Stud	2"x4"x96"	6	each
Opening Header Window	2"x10"x3'3"	4	each
Opening Header Door	2"x10"x5'6"	2	each
Wall Plate	2"x4"	165	feet
Opening Rough Sill	2"x4"x3'0"	2	each
Wall Sheathing	0 1/2"x4'0"x8'0"	15	shts
Common Rafter	2"x6"x2'3"	8	each
Common Rafter	2"x6"x3'9"	8	each
Common Rafter	2"x6"x5'3"	8	each
Common Rafter	2"x6"x8'0"	8	each
Common Rafter	2"x6"x10'0"	10	each
Fascia Board	2"x6"	68	feet
Hip Rafter	2"x8"x12'0"	4	each
Ridge Board	2"x8"	4	feet
Ring Joist (Ceiling)	2"x6"	56	feet
Joist (Ceiling)	2"x6"x12'0"	11	each
Roof Sheathing	0 3/4"x4'0"x8'0"	10	shts
Plywood H-Clip		40	each
Attic Vent		2	each
Fascia Cladding	5 1/2"	68	feet
Eave Start		68	feet
Soffit		94	sqft
Roofing Felt		1	rolls
Asphalt Shingles		10	bndl
Ridge Shingles		49	feet
36X48 DOUBLE HUNG 1	3'0"x4'0"	2	each
60X80 COLONIAL B 2	5'0"x6'8"	1	each
Entrance Hardware		2	each
Shims		1	bund
R-12 Wall Insulation	3 1/2"	359	sqft
Vapor Barrier (Wall)		430	sqft
Siding		372	sqft
Siding Starter		57	feet
Siding J-Molding		36	feet
Siding Drip-cap		12	feet
Outside Siding Corner		31	feet
Door Casing	4"	20	feet
Window Casing	4"	34	feet
4x4 Treated Post	4'x4"x16'	4	each